INSTITUTO DE CIENCIAS DE LA CONSTRUCCIÓN EDUARDO TORROJA

C/ Serrano Galvache nº 4 28033 Madrid

Tel.: (34) 91 302 04 40 Fax: (34) 91 302 07 00 director.ietcc.@csic.es www.ietcc.csic.es





MIEMBRO DE LA EOTA EOTA MEMBER

EUROPEAN TECHNICAL APPROVAL

ETA - 10/0162

(English language translation, the original version is in Spanish language)

Nombre comercial:

Trade name:

Beneficiario del DITE

Holder of approval:

Área genérica y uso del producto de construcción :

Generic type and use of construction product:

Validez de :

hasta:

Validity from / to:

El presente Documento de Idoneidad Técnica Europeo contiene:

This European Technical Approval contains:

HYPERTECTUM

ETS EUROPE BVBA Doggenhoustraat n° 3, B-2520 Ranst Antwerpen- Belgium

Sistema de Impermeabilización de Cubiertas Aplicado en forma Líquida, basado en Poliuretanos

Liquid Applied Roof Waterproofing Kit, based on Polyurethane

5 April 2014 2 December 2018

10 páginas, incluyendo 1 anexo, el cual forma parte del documento

10 pages including 1 annex which form an integral part of the document



I. LEGAL BASES AND GENERAL CONDITIONS

- 1. This European Technical Approval is issued by the **Instituto de Ciencias de la Construcción Eduardo Torroja** in accordance with:
 - Council Directive (89/106/EEC)¹ of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products, modified by the Council Directive 93/68/EEC of July 1993².
 - Real Decreto 1630/1992 de 29 de diciembre, por el que se dictan disposiciones para la libre circulación de productos de construcción en aplicación de la Directiva 89/106/CEE³. REAL DECRETO 1328/1995, de 28 de julio, por el que se modifican, en aplicación de la Directiva 93/68/CEE las disposiciones para la libre circulación, aprobadas por el Real Decreto 1630/1992, de 29 de diciembre. (B.O.E. 19.895) y la Orden CTE/2276/2002 de 4 de septiembre.
 - Common Procedural Rules for Requesting, Preparing and the Granting of European Technical Approvals set out in the Annex of Commission Decision 94/23/EC⁴.
 - Guideline for European Technical Approval of Liquid applied roof waterproofing kits, ETAG 005, edition 2000, Part 1 "General" and Part 6 "Specific stipulations for kits based on polyurethane".
- 2. The Instituto de Ciencias de la Construcción Eduardo Torroja is authorised to check whether the provisions of this European Technical Approval are met. Checking may take place in the manufacturing plant(s) (e.g. concerning the fulfilment of assumptions made in this European Technical Approval with regard to manufacturing). Nevertheless, the responsibility for the conformity of the products to the European Technical Approval and for their fitness for intended use remains with the holder of the European Technical Approval.
- 3. This European Technical Approval is not to be transferred to other manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those / indicated on page 1/ laid down in the context of this European Technical Approval.
- 4. This European Technical Approval may be withdrawn by the *Instituto de Ciencias de la Construcción Eduardo Torroja* pursuant to Article 5.1 of the Council Directive 89/106/EEC.
- 5. Reproduction of this European Technical Approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of the *Instituto de Ciencias de la Construcción Eduardo Torroja*. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European Technical Approval.
- 6. The European Technical Approval is issued by the Approval Body in its official language. This version corresponds to the version circulated within EOTA. Translations into other languages have to be designated as such.

¹ Official Journal of the European Communities no L 40, 11.2.1989, p.12

² Official Journal of the European Communities no L 220, 30.8.1993, p.1

³ Boletín Oficial del Estado nº 34 de 9 de febrero de 01993.

⁴ Official Journal of the European Communities no L 17, 20.1.1994, p.34

II SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

1 Definition of product and intended use

1.1 Definition of product

The liquid applied roof waterproofing kit, based on polyurethane "HYPERTECTUM" consists of a polyurethane resins, mono-component, elastomeric without internal protection layer; which once polymerised conforms an elastic lining, in form of a layer completely bonded to the support (concrete, mortar, ceramic).

The minimum layer thickness of the assembled system has to be 1,2 mm and the quantity consumed larger than 1.5 kg/m².

The kit contents an internal layer (geo-textile) as enforcement of the membrane and an external protection HYPERTECTUM TOPCOAT, for a P3 category for user loads and working life of 10 years (minimum consume 150 g/m²).

The annex 1 shows the components and the system build-up of the system.

1.2 Intended use

The intended use of this System is the waterproofing of roof against the water, as in liquid as vapour form. This LARWK fulfils the Essential Requirements n° 2 (Safety in case of fire), n° 3 (Hygiene, health and the environment) and n° 4 (Safety in use) of the Construction products directive 89/106/EEC.

The performance levels of this System according to the Guide ETAG 005⁵ Part. 1 and Part. 6 are included in the annex 1.

The provisions made in this European Technical Approval (ETA) are based on an assumed intended working life of the system of 10 years (W2) with HYPERTECTUM TOPCOAT and 25 years (W3).

The indication given on the working life cannot be interpreted as a guarantee given by the manufacturer, but are only to be regarded as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

"Assumed intended working life" means that, when an assessment following the ETAG provisions is made, and when this working life has elapsed, the real working life may be, in normal use conditions, considerably longer without major degradation affecting the Essential Requirements.

2. Characteristics of product and methods of verification

The assessment of the fitness of the liquid waterproofing kit HYPERTECTUM for the intended use regard to the Essential Requirements n° 2, 3 and 4 was performed in compliance with the "Guideline for European Technical Approval of liquid applied roof waterproofing kits", ETAG 005, edition 2000, Part 1: General and Part 6: Specific stipulations for kits based on polyurethane.

2.1 Characteristics of System "HYPERTECTUM"

2.1.1 ER. 2 Safety in case of fire

External fire performance. Classification: B_{roof}(t1) according to EN 13501-5 for supports included in point 1.1.

Reaction to fire. Euroclass F

⁵ ETAG N° 5, "Liquid applied roof waterproofing kits", Official Journal of the European Communities N° C 212/02, 06.09.2002.

2.1.2 ER. 3 Hygiene, health and environment

Resistance to water vapour (EN 1931). μ = 700- 2.000

Watertightness (EOTA TR-003). Watertight

Statement of dangerous substances. According to the manufacture's declaration taking account of the EU database, the product installed does not contain and release any dangerous substance.

Resistance to wind loads (EOTA TR-4). Pass (>50 KPa)

Resistance to dynamic indentation (EOTA TR- 6). Resistance Level: I₃

Resistance to static indentation (EOTA TR-7). Resistance Level: L4

Resistance to fatigue movement (1.000 cycles) (EOTA TR-8). Pass

Resistance to low temperatures effects (-20°C). Dynamic indentation, Resistance Level: I₃

Resistance to high temperatures effects (90°C). Static indentation

T°C	Load (N)	Resistance level
90°C	70	L1
80°C + HYPERTECTUM TOPCOAT	200	L3

Resistance to heat ageing (EOTA TR-11). The samples are exposed to 80°C during 200 days.

Fatigue movement	pass
Dynamic indentation (-20°C)	14
Tensile strength (MPa) (EN-ISO 527-3) (unreinforced)	3,7
Tensile elongation (%) (EN-ISO 527-3) (unreinforced)	213

Resistance to UV-radiation in the presence of moisture (EOTA TR- 10). The samples are exposed 5000 hours to UV-radiation.

Tensile strength (MPa) (EN-ISO 527-3)	8
Tensile elongation (%) (EN-ISO 527-3)	500
Dynamic indentation (-10°C)	l ₃

Resistance to hot water ageing (EOTA TR-12). The samples are kept in touch with water at 60°C over 30, 60 and 180 days.

Ages	T°C	Load (N)	Resistance level
30 d	80°C With HYPERTECTUM	200	L3
60 d	90°C	70	L1
180 d	30°C	70	L1

Resistance to wind loads Pass (>50 KPa)

Resistance to plant roots (EN 13948). NPD

2.1.3 ER. 4 Safety in use

Slipperiness. NPD

2.1.4 Related aspects of serviceability

Effect of weather conditions. The system does show changes in its tensile properties, when the system is assembled and cured under two temperature conditions of 0°C and 40°C, but these values obtained complied with the manufacturer's specifications (pass).

Effect of day joints. The delamination strength test performed on a layer assembled over other one, it shows a good delamination strength, being upper to required value of 50 KPa. (pass).

2.2 Identification of components

The characteristics of the components of this System show the following values, which compliance with their respective tolerances stated in the Manufacture Technical Dossier (MTD).

- Waterproofing liquid constituted by poliol and isocianates, with loads and pigments mineral, and additives (anti-air entering, biocides, etc.). The main characteristics of this waterproof liquid are:

Density (g/cm³) (ISO 1675)	1.3-1.4 g/cm ³
Dry extract (105°C) (% weight) (EN 1768)	> 85 %.
Ash content (450°C) (% weight) (EN 1879)	40-45 %.
Viscosity (cps) (EN-UNE ISO 2555)	2.000 -8.000 cps

- Internal layer by geotextil, used as reinforcement in the specific details

Mass per unit area (g/m²) (EN 29073-1)	80-120
Tensile elongation (%)	> 35 (L)
(EN 10319)	> 40 (T)
Tensile strength (N/5cm)	>3 (L)
(EN 10319)	>4 (T)

- HYPERTECTUM TOPCOAT, External protection. Aliphatic Polyurethane resins.

Density (g/cm³), (EN ISO 1675)	0,95-1,03
Viscosity (cps), (ASTM D 1200)	90-100

3 Evaluation of Conformity and CE marking

3.1 Attestation of Conformity System

The European Commission according to her decision (98/599/EC of October 1998, Official Journal of the European Communities N° L 287, 24.10.1998) on the procedure of attestation of conformity has laid down for this type of material

System 3

for the procedure of attestation of conformity (Annex III, clause 2(ii) second possibility of Directive 89/106/EEC) for liquid applied roof waterproofing kits. According to this decision, system 3 of Attestation of Conformity also applies with regard to external fire performance.

The system 3 provides:

- a) Tasks for the manufacturer: Factory production control.
- b) Tasks for the approved body: Initial type-testing of the product.

3.2 Responsibilities

3.2.1 Tasks for the manufacturer

3.2.1.1 Factory production control

The manufacturer exercises a permanent internal control of production and assures that the obtained results fulfil the quality level demanded. All the elements, requirements and provisions adopted by the manufacturer are documented in a systematic manner in the form of written policies and procedures. This control production system documentation ensures a common understanding of quality assurance and enables the achievement of the required product characteristics according to the Technical European Approval.

The manufacturer shall only use incoming materials supplied with the relevant inspection documents according to the MTD.

The results of the factory production control shall be recorded and evaluated in accordance with the provisions of the "control plan" (6). The records shall include at least the following information:

- Name of the product and of the initial materials,
- type of inspection or control,
- date of manufacture of the product, batch N° if needed, and date of inspection or control of the product or of the initial materials,
- result of inspections or controls and, as far as applicable, comparison with the requirements,
- signature of the person responsible for the factory production control.

The records shall be kept for at least five years. Further information concerning test, frequency and tolerance are included in the control plan, which is part of the MTD to this ETA placed at IETcc.

3.2.1.2 Other tasks of the manufacturer

For initial type – testing, the results of the tests performed as part of the assessment for the ETA shall be used unless there are changes in the production line or plant. In such cases the necessary initial type- testing has to be agreed with the IETcc.

The manufacturer shall, on the basis of a contract, involve a body which is notified for the tasks referred to in section 3.1 in the field of the product in order to undertake the actions laid down in the clause 3.2.2. For this

⁶ The control plan is a confidential part of the European Technical Approval and only handed to the notified body involved in the procedure of attestation of conformity. The control plan has been agreed between the manufacturer and de IETcc and it is laid down in the context of the MTD and deposited at the IETcc

purpose, the control plan referred to in sections 3.2.1.1 shall be handed over by the manufacturer to the notified bodies involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this ETA.

3.2.2 Tasks for the Approved Body

3.2.2.1 Initial type-testing of the product

The initial type-testing have been conducted by the IETcc to issued this ETA in accordance with chapter 5 of the guideline "Liquid applied roof waterproofing kits" (ETAG 005) part 1 and 6.

The verifications underlying this ETA have been furnished on samples from the current production; these will replace the initial type-testing carried out by the manufacturer.

The IETcc has assessed the results of these tests in accordance with chapter 6 of this ETA –Guideline, as part of the ETA issuing procedure.

3.3 CE marking

The CE marking⁷ shall be affixed on the pot of the kit of the roof waterproofing "HYPERTECTUM".

In addition to the symbol "CE" the following information shall be given:

- name or identifying mark of the manufacturer and of the factory,
- short definition of the levels of performance (ETAG 005-8), according to annex 1,
- the last two digits of the year in which the CE marking was affixed,
- number of the European technical approval,
- number of the European technical approval Guideline,

4 Assumptions under which the fitness for use of the product for the intended use was favorably assessed

4.1 Manufacture

Further information about the manufacturing of the kit is laid down in the MTD placed at IETcc.

This ETA is issued for the kit "HYPERTECTUM" on the basis of the product composition deposited at IETcc. Changes to the components of the kit or in the production process of the components, which could result in the production process and/or the properties of the product deposited being incorrect should be notified to IETcc before the changes are introduced. IETcc will decide whether or not such changes affect the ETA and consequently the validity of the CE marking on the basis of the ETA and if further assessment/alterations to the ETA shall be necessary.

This approval may be extended with other requirements applicable to dangerous substances resulting from transposed European legislation or applicable national regulations and administrative provisions.

Besides, this approval may be extended with other requirements applicable to the products resulting from other applicable national regulations and administrative provisions.

These requirements need also to be complied with.

⁷ Notes on the CE marking are stated in Guidance Paper D "CE marking under the Construction Products Directive", Brussels 01 August 2002

4.2 Design

The fitness of the respective use for the levels of performance of this System stated in Annex 1 complies with the Spanish national requirements.

In the MTD the manufacture gives information on the quantities consumed and the processing, which shall lead to a thickness of the roof waterproofing of at least 1.4 mm.

4.3 Installation

The fitness of use of this kit can only be assumed if this is installed according to he manufacturer's instructions, which are part of the MTD to this ETA placed at IETcc.

Particularly, it is recommended to consider:

- The kit installation has to carried out by qualified installers,
- it can only be used the components of the kit indicated in this ETA,
- the supervision of the amount of material used (kg/m²) and the control visual to check that each coat cover totally the one below, can ensure the minimum thickness of the kits,
- inspection of the roof surface (cleanliness and correct preparation) before applying the roof waterproofing,
- the recommended temperature of the product to be assembled will be between 0°C and 40°C and it will be not admitted support temperatures upper to 45°C. In other conditions it will need to follow the manufacturer's instructions.

Before, the installation of HYPERTECTUM, it is recommended to read its security card.

4.4 Manufacturer's responsibilities

It is responsibility of the manufacturer of the product to ensure that the information on all provisions is given to those concerned.

5 Information by the manufacture

5.1 Recommendations on packing, transport and storage

This product is considered inflammable, so it is necessary to follow the security instruction for transport and handle.

The storage must be done at temperatures between 0°C - 45°C, in dry conditions and protected against the sun radiation.

The product must be used 1 year after manufacturing date. Once the pot is opened, the product must be consumed in a week.

Further installation details are laid down in the MTD place at IETcc.

5.2 Recommendations on use, maintenance and repair

In those roofs with deteriorated areas of the waterproof layers, they will be repaired removing all the deteriorated layers. Afterwards, the new product will be assembled following the installation instruction and the new coats must overlap, at least 3 cm, to the coat no deteriorated.

Further installation details are laid down in the MTD place at IETcc.



Instituto de Ciencias de la Construcción Eduardo Torroja CONSEJO SUPERIOR DE INVESTIGACIONES CIENTÍFICAS

c/ Serrano Galvache nº4. 28033 Madrid. Tel: (34) 91 302 04 40 Fax. (34) 91 302 07 00 www.ietcc.csic.es




On behalf of the Instituto de Ciencias de la Construcción Eduardo Torroja

Madrid, 5 April 2010

EL DIRECTOR DEL INSTITUTO DE CIENCIAS DE LA CONSTRUCCIÓN EDUARDO TORROJA

Víctor R. Velasco

Annex 1. System build-up of the roof waterproofing "HYPERTECTUM"



Characteristics of the System "HYPERTECTUM"

Minimum thickness	1.2 mm
Water vapour diffusion resistant factor	μ ≈ 1105
Resistance to wind loads	> 50 KPa
Resistance to plant roots	NPD
Statement on dangerous substances	Does not contain any
Resistance to slipperiness	NPD

Performance levels according to the intended use

	HYPERTECTUM	HYPERTECTUM + HYPERTECTUM TOPCOAT
External fire performance	Broof (t1)	
Fire reaction	Clase F	
Expected working life	W3 (25 years)	W2 (10 years)
Climatic zone of use	S (Severe)	
User loads	P1	P3
Roofs slopes	S1 – S4	
Minimum surface temperatures	TL3 (- 20 °C)	
Maximum surface temperatures	TH4 (90°C)	TH3 (80°C)